



SAGARA HOSPITAL PUNNAPRA

(Under the Co-operative Academy of Professional Education, Estd.by Government of Kerala)

നം: SH/AE/1313/2018

തീയതി 1/09/2018

കാട്ടേഷൻ നോട്ടീസ്

പുനപ്രസാഗരസഹകരണആശുപത്രിയിൽ സ്റ്റൈനോകാർഡിയോസ്കോപ്പിക് സർജറിയിൽ സ്പെഷ്യാലിസ്റ്റായ ഡോ. സി.എ.എ.യുടെ നേതൃത്വത്തിൽ പരിചയമുള്ള സ്ഥാപനങ്ങൾ/വ്യക്തികൾ എന്നിവരിൽ നിന്നും കാട്ടേഷനുകൾ ക്ഷണിച്ചുകൊള്ളുന്നു. കാട്ടേഷനിൽ പങ്കെടുക്കാൻ താൽപ്പര്യമുള്ളവർ കാട്ടേഷൻ ഷെഡ്യൂൾ പൂരിപ്പിച്ച് മുദ്രവെച്ച കവറിൽ 12.09.2018 ഉച്ചയ്ക്ക് 3 മണിക്ക് മുൻപായി അഡ്മിനിസ്ട്രേറ്റർക്ക് നേരിട്ടോതപാൽ മുഖാന്തിരമോ സമർപ്പിച്ചിരിക്കണം. കാട്ടേഷൻ ഷെഡ്യൂൾ www.sagarahospital.org യിൽ നിന്നോ ആശുപത്രി ഓഫീസിൽ നിന്നോ എല്ലാ പ്രവൃത്തിദിവസങ്ങളിലും രാവിലെ 10 മുതൽ വൈകുന്നേരം 5 മണി വരെ ലഭിക്കുന്നതാണ്. കാട്ടേഷനുകൾ 12.09.2018, 4 മണിക്ക് കാട്ടേഷനുകൾ സമർപ്പിച്ചവരുടെ സാന്നിധ്യത്തിൽ തുറന്ന് പരിശോധിക്കുന്നതാണ് എസ്റ്റിമേറ്റ് തുക 29,690/ വിശദവിവരങ്ങൾക്ക് ഫോൺ: 04772240229.


 സെക്രട്ടറി 1/9/18



- പകർപ്പ് :
1. ബ്ലോക്ക് പഞ്ചായത്ത് ഓഫീസ്, അമ്പലപ്പുഴ
 2. ഗ്രാമപഞ്ചായത്ത് ഓഫീസ്, പുനപ്ര നോർത്ത്
 3. വില്ലേജ് ഓഫീസ്, പാവൂർ.
 4. നോട്ടീസ് ബോർഡ്.

Vadackal P.O., Alappuzha - 688 003. Reg No: BI-2375/2017
 Phone : (Off) 0477 2269976,2240229. (Enq) 0477 2267676,2240200,203
 E-mail id : sagarahospital@gmail.com, Website : www.sagarahospital.org

**PROVIDING CHANGE ROOM AT UNDER SIDE OF STAIR AT GROUND FLOOR OF SAGARA HOSPITAL
PUNNAPRA**

QUOTATION SCHEDULE

SI: NO	Description	Unit	Qty	Rate	Amount
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Zsections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron) (SH NO 21.1.1.2)	Kg	34.45	579.2	19953.44
2	Providing and fixing 10 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides (SH NO 21.2.2)	m2	9.31	795.11	7402.474
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. With float glass panes of 4.0 mm thickness (SH No 21.3)	m2	1.1	1270.72	1397.79
4	Providing and fixing IS : 12817 marked stainless steel butt hinges 50x37x1.50 mm with stainless steel screws etc.	E	3	50.6	151.8
5	Providing and fixing tower bolt including all cost of conveyance ,labour charges etc complete.	E	1	70.35	70.35
6	Providing and fixing bright finished 100 mm mortice lock with 6 levers without	E	1	714.44	714.44
TOTAL					29690
(Rupees Twenty Nine Thousand Six Hundred and ninety only)					

I/We agree to execute the work at % above estimate rate/below estimate rate/estimate rate.

CONTRACTOR

ADMINISTRATOR